

MONITORING REPORT FORM (CDM-MR) *
Version 01 - in effect as of: 28/09/2010

CONTENTS

- A. General description of the project activity
 - A.1. Brief description of the project activity
 - A.2. Project participants
 - A.3. Location of the project activity
 - A.4. Technical description of the project
 - A.5. Title, reference and version of the baseline and monitoring methodology applied to the project activity
 - A.6. Registration date of the project activity
 - A.7. Crediting period of the project activity and related information
 - A.8. Name of responsible person(s)/entity(ies)
- B. Implementation of the project activity
 - B.1. Implementation status of the project activity
 - B.2. Revision of the monitoring plan
 - B.3. Request for deviation applied to this monitoring period
 - B.4. Notification or request of approval of changes
- C. Description of the monitoring system
- D. Data and parameters monitored
 - D.1. Data and parameters used to calculate baseline emissions
 - D.2. Data and parameters used to calculate project emissions
 - D.3. Data and parameters used to calculate leakage emissions
 - D.4. Other relevant data and parameters
- E. Emission reductions calculation
 - E.1. Baseline emissions calculation
 - E.2. Project emissions calculation
 - E.3. Leakage calculation
 - E.4. Emission reductions calculation
 - E.5. Comparison of actual emission reductions with estimates in the registered CDM-PDD
 - E.6. Remarks on difference from estimated value

* as contained within the document entitled "Guidelines for completing the monitoring report form (CDM-MR)" (EB 54 meeting report, annex 34).

MONITORING REPORT
Version 04; 23/08/2012

**TITLE: “N₂O ABATEMENT PROJECT AT NITRIC ACID PLANT NO. 11 AT AFRICAN
EXPLOSIVES LTD. (AEL), SOUTH AFRICA”**

Reference Number: 1364

Monitoring period: No 04, 01/03/2011 – 06/08/2011

SECTION A. General description of the project activity

A.1. Brief description of the project activity:

Purpose of the project activity and measures taken to reduce GHG emissions

The sole purpose of the project activity is to significantly reduce former levels of N₂O emissions from the production of nitric acid at AEL's nitric acid plant No. 11 (“AEL-11”) in Johannesburg , Modderfontein, South Africa, by implementation of a secondary N₂O abatement catalyst.

Brief description of the installed technology and equipments

The employed secondary N₂O abatement catalyst technology is supplied by Johnson Matthey plc who exclusively markets a secondary catalyst technology that has been developed by YARA International ASA (Norway). Continuous monitoring of emission reductions is assured by an Automated Measuring System (AMS), consisting of stack gas volume flow meter, N₂O Analyzer, and respective data logging facilities. The AMS as well as its installation complies with the requirements of the European Standard EN 14181 as required by the methodology.

Relevant dates for the project activity

Registration Date: 08/02/2008

Installation of AMS: January 2006 (The N₂O analyser was replaced in September 2007, after the baseline measurement). Because of some technical difficulties with the Environnement MIR9000 analyser on the No. 9 plant, AEL has decided to install two completely new analysers (ABB Uras 14) in both the No. 9 and the No. 11 plant in 2007.)

Baseline Campaign: BL – Campaign 20/07/2006 – 18/02/2007

Intermediate campaign without secondary catalyst: 25/02/2007- 18/08/2007

Installation of secondary catalyst: 12/09/2007

Starting Date of Crediting period: 08/02/2008

Project Campaigns:	1. Campaign	PC1 - 12/09/2007-19/03/2008
	2. Campaign	PC2 - 20/03/2008-28/09/2008
	3. Campaign	PC3 - 04/10/2008-23/05/2009
	4. Campaign	PC4 - 08/06/2009-27/12/2009
	5. Campaign	PC5 - 30/12/2009-03/08/2010
	6. Campaign	PC6 – 04/08/2010-16/11/2010
	7. Campaign	PC7 - 19/11/2010-28/02/2011

Project Campaigns covered by current Monitoring/Verification Period:

8. Campaign PC8 – 24/03/2011-06/08/2011

Total emission reductions achieved in this monitoring period

The total amount of emission reductions achieved in this monitoring period is 69,230 t CO₂e.

A.2. Project Participants

Name of Party involved (host) indicates a Host Party	Private and/or public entity(ies) project participants (as applicable)	Kindly indicate if the Party involved wishes to be considered as project participant (Yes/No)
South Africa (host)	African Explosives Ltd (“AEL”)	No
United Kingdom of Great Britain and Northern Ireland	<ul style="list-style-type: none">• N.serve Environmental Services GmbH, Germany (“N.serve”)• Electrabel NV/SA	No
Switzerland	<ul style="list-style-type: none">• N.serve Environmental Services GmbH• African Explosives Ltd.	No

A.3. Location of the project activity:

The project activity is located in: Modderfontein (approx. 20 km north-east of Johannesburg). Postal address: PO Modderfontein 1645. Coordinates of the plant are 26°05'50'' South and 28°10'26'' East.

A.4. Technical description of the project

The project activity entails the installation and implementation of the following technical equipment and quality measures:


- 1.) secondary N₂O abatement technology
- 2.) Automated Monitoring System (AMS) for continuous N₂O measurement which is fully in compliance with European Standard EN 14181 (see Section C for more detail)
- 3.) training of local staff on installation, operation and maintenance of catalyst and monitoring equipment, etc. as well as implementation of quality check and quality assurance measures (see Section C for more detail)

Catalyst Technology

AEL has contracted with Johnson Matthey plc who exclusively markets a secondary catalyst technology that has been developed by YARA International ASA (Norway). AEL has contracted with Johnson Matthey plc to install the YARA 58 Y 1® catalyst system consisting of an additional base metal catalyst that is installed below the standard precious metal gauze pack. This technology has been implemented inside the AEL-11 ammonia oxidation reactor.

The precious metal gauze pack – i.e. the primary catalyst required for the actual production of nitric acid – has been supplied to AEL by W.C. Heraeus for a number of years. The precious metal composition of that gauze pack remains unchanged during the crediting period of the project.

A secondary catalyst will reduce N₂O levels in the gas mix resulting from the primary ammonia oxidation reaction. A wide range of metals (e.g. Cu, Fe, Mn, Co and Ni) have shown to be of varied effectiveness in N₂O abatement catalysts. The YARA 58 Y 1® abatement catalyst is made of cylindrical pellets containing cobalt as an active ingredient. The catalyst has been tried and tested in a number of nitric acid plants in Europe. The abatement efficiency has been shown to be in the range of 70 - 90% in the following reaction:




If operated properly, the secondary catalyst system has a lifetime of several campaigns and may reduce N₂O emissions to a level satisfactorily below the baseline for about two years, before the catalyst material needs to be replaced. The YARA 58 Y 1® abatement catalyst does not contaminate the nitric acid produced in the respective nitric acid plant, neither with Cobalt nor with any of the other catalyst materials. It does not require additional heat or other energy input, because the temperature levels

present inside the Ammonia Oxidation Reactor suffice to ensure its optimum abatement efficiency. There are no additional greenhouse gases or other emissions generated by the reactions at the N_2O abatement catalyst.

N_2O abatement catalyst installation

The secondary catalyst itself is easily installable during a routine plant shut-down and gauze change. The pellets are poured into the support basket / heat shield arrangement and raked level. The gauze pack is then installed above this bed using the support mechanism provided by the heat shield.



AEL's nitric acid plant No.11 operates at a pressure of around 4.5 bars (gauge) inside the ammonia oxidation reactor. Through the introduction of the secondary catalyst into the ammonia reactor, a slight pressure drop (ΔP) is expected to occur. This ΔP may lead to a very slight reduction in ammonia conversion efficiency and hence a very small reduction in nitric acid output. In practice, this loss of production will be insignificant.

A.5. Title, reference and version of the baseline and monitoring methodology applied to the project activity:

This project activity is based on Approved Baseline and Monitoring methodologies AM0034 (Version 2): "Catalytic reduction of N_2O inside the ammonia burner of nitric acid plants". Furthermore, the project draws on approved baseline methodology AM0028 (Version 04.2) for the baseline scenario selection and employs the "Tool for the demonstration and assessment of additionality" (Version 02).

A.6. Registration date of the project activity:

Registration Date of project activity: 08/02/2008

A.7. Crediting period of the project activity and related information (start date and choice of crediting period):

Crediting period: 10 years; Start date: 08/02/2008

A.8. Name of responsible person(s)/entity(ies):

Contact information of the person(s)/entity(ies) responsible for completing the monitoring report form (CDM-MR).

Mr. Martin Stilkenbäumer (stilkenbaeumer@nserve.net)

N.serve Environmental Services GmbH
Grosse Theaterstrasse 14
20354 Hamburg, Germany

Phone: +49 40 309 978 614

Fax: +49 40 309 978 610

SECTION B. Implementation of the project activity

B.1. Implementation status of the project activity

>>

The determination of the permitted operating conditions for operating temperature, operating pressure, maximum ammonia flow rate, maximum ammonia to air ratio, normal campaign length, normal gauze supplier and normal gauze composition was undertaken by the validating DOE (as it was clarified by the CDM EB in EB31 meeting that either the validating or verifying DOE could undertake the task of determination of the permitted operating conditions). However, the verification of the baseline campaign as well as the determination of the baseline emission factor was in the scope of the verifying DOE.

A baseline campaign was operated from 20/07/2006 to 18/02/2007, which was used towards ex-ante estimate of emission reduction in the PDD as confirmed in the validation report, the data from this baseline campaign were not verified by the validating DOE, and the confirmation of the baseline campaign data to be used for ex-post emission reduction calculations was included in the scope of the verifying DOE for the first verification. After the baseline campaign was completed, the project entity decided not to install the secondary catalyst yet to avoid incurring additional costs while the CDM validation process was still on going. This resulted in an intermediate campaign without secondary catalyst from 25/02/2007 to 18/08/2007. The project was submitted for registration on September 2007, and the first project campaign with secondary catalyst started on 12/09/2007 as the project was likely to get registered during this campaign.

The project got registered by UNFCCC on the 08/02/2008, which is the starting date of the project activity as well as for the crediting period.

As to the characteristics of this specific project type certain production related events and incidents may affect the performance of the project or influence the monitoring of emission reductions in addition to possible failure of the installed monitoring equipment. The below table and lists demonstrate all relevant events and incidents related to production and/or emission monitoring which have occurred during actual operation within this specific monitoring period, as well as the measures taken for addressing any resulting problems and issues.

#	Start of the event	End of the event	Campaign		Short description
			AEL designation	Project campaign	
1	24/03/2011		C24	8	Installation of new gauze and start-up
2	25/03/2011	25/03/2011	C24	8	Turning device not working and tripped on ratio
3	26/03/2011	26/03/2011	C24	8	Plant rate unsteady and governor faulty.
4	15/04/2011	16/04/2011	C24	8	Plant trip power failure
5	18/04/2011	23/06/2011	C24	8	Leakage in N ₂ O sampling system. The NCSG data for the period 18/04/2011 03:00 hours until 23/06/2011 02:00 hours was excluded from the calculation of the NCSG average value for that campaign.
6	04/05/2011	04/05/2011	C24	8	Plant tripped on absorption level high high alarm Waited for steam and build column level
7	05/05/2011	05/05/2011	C24	8	Tripped due to control oil pressure low low alarm. Instrument checking oil system.

					Waited for column level to build up.
8	06/05/2011	06/05/2011	C24	8	Problems with control oil system. Column level build up.
9	08/05/2011	09/05/2011	C24	8	Low control oil pressure
10	10/05/2011	10/05/2011	C24	8	Tripped due to control oil pressure low low alarm.
11	11/05/2011	12/05/2011	C24	8	Control oil problems. Steam leaks,governor and instrument equipments under maintenance.
12	20/05/2011	21/05/2011	C24	8	Plant trip
13	02/06/2011	03/06/2011	C24	8	Plant trip
14	30/06/2011	01/07/2011	C24	8	Plant trip
15	01/08/2011	02/08/2011	C24	8	Plant trip
16	06/08/2011		C24	8	Plant stop – gauze change

NO events or incidents of any relevance in regard to impacting the applicability of the methodology occurred during this monitoring period.

No events or incidents that resulted in AMS downtime occurred during this monitoring period or during the baseline campaign period. Per AM0034 no correction is needed for the plant downtime periods.

B.2. Revision of the monitoring plan

>>

The monitoring plan has not been revised.

B.3. Request for deviation applied to this monitoring period

>>

NO deviation was applied to this monitoring period.

B.4. Notification or request of approval of changes
--

>>

NO notifications or request of approval of changes from the project activity as described in the registered CDM-PDD have been made.

SECTION C. Description of the monitoring system

>>

1. General Description of the AMS (ABB URAS 14)

A complete Automated Monitoring System (AMS) to monitor the mass emissions of N_2O at the stack of AEL's No.11 nitric acid plant was installed and has been operated since January 2006. The Manufacturer and type of the first N_2O Analyser was Environnement S.A. MIR 9000. After the measurements for the baseline campaign were completed it was replaced by a ABB AO2040 Uras 14 NDIR analyser in 2007. Because of some technical difficulties with the Environnement MIR9000 analyser on the No. 9 plant, AEL has decided to install two completely new analysers in both the No. 9 and the No. 11 plant in 2007 (as described in the PDD).

2. Sample point

The location of the sample point was selected to provide ease of access and a location close to the analyser. The most suitable position is in tail gas of the plant downstream of all process equipment.

3. Sample Conditioning System

The gas sample is continuously taken via a heated probe and filter unit and a heated sample line. Before entering the analyzer the gas is treated by a dryer unit to avoid possible moisture effects.

4. Analyser

NCSG measurements: Environnement S.A. MIR 9000 (during baseline Campaign), ABB AO2040 Uras 14 (during project campaigns).

5. Flow Meter


The Emerson Rosemount Flow Meter Annubar®, model no. 485, relies on the Averaging Pitot Tubes (APTs).

The Rosemount Annubar® 485 is a device used to measure the flow-velocity of a liquid, gas or steam fluid that passes through a pipe. It measures by creating a differential pressure (DP) that is proportional to the square of the velocity of the fluid in the pipe, in accordance with Bernoulli's theorem. This DP is measured and converted into a flow rate using a secondary device, such as a DP pressure transmitter.

The Annubar generates a DP by partially blocking the flow. The velocity of the fluid is decreased and stalled as it reaches the upstream surface of the Annubar sensor, thus creating the Impact Pressure. The Rosemount 485 Annubar® senses the impact pressure by utilizing a frontal slot design, which opens into the high pressure chamber.

This high pressure chamber connects directly into the DP transmitter for measurement.

As the fluid continues around the Annubar sensor, it creates a lower velocity profile on the back of the sensor, creating the low/suction pressure downstream. Individual ports, located on the backside of the Annubar sensor measure this low pressure. Working on the same principle as with high pressure, an average low pressure value is obtained in the low pressure chamber that connects directly into the transmitter for measurement. The resulting differential pressure is the difference between the impact (high) pressure reading and the suction (low) pressure reading as seen below.



6. Monitoring plan and responsibilities

The emission reductions achieved by the project activity are monitored based on the Approved baseline and monitoring methodology AM0034 (Version 2) “Catalytic reduction of N₂O inside the ammonia burner of nitric acid plants” as prepared by N.serve Environmental Services GmbH.

AM0034 requires the use of the European Standard EN14181 (2004) “Stationary source emissions - Quality assurance of automated measuring systems” as a guidance for installing and operating the Automated Monitoring System (AMS) in the nitric acid plants for the monitoring of N₂O emissions.

As an operator of nitric acid plants since 1932 and of the No. 11 nitric acid plant since 1979, AEL staff in general and its Instrument Department in particular is accustomed to operating technical equipment to a high level of quality standards.

The Production Manager (PM) has the overall responsibility for the ongoing operation of the project.

The Engineering Team Manager Electrical/Instrument (ETM E/I) is responsible for the day-to-day calibration procedure and any adjustments required to the instruments as a result of the calibrations.

The Process Controller (PC) checks the analyser regularly for any abnormal occurrences. These checks are done using a plausibility checklist, which is filled in and filed, in the control room. If there are any problems the ETM E/I is notified so that the problem can be rectified.

Operation, maintenance, calibration and service intervals are being carried out by staff from the instrumentation department according to the vendor’s specifications.

All monitoring procedures at AEL are also conducted and recorded in accordance with the well established procedures under ISO 9001/14001 which is regularly audited by the South African Bureau of Standards, an independent auditing firm accredited for ISO 9001/14001 certification.

AEL derives hourly averages for all of the monitored parameters and delivers these data to N.serve. N.serve is responsible for the correct analysis of the delivered data in accordance with the methodology.

7. Application of EN 14181 procedures to the project

In the following, it is described how the procedures given in EN14181 for QAL1, 2 and 3 have been practically applied at AEL No. 11 plant.

QAL 1

In accordance with EN 14181 an AMS shall have been proven suitable for its measuring task (composition of the flue gas) by use of the QAL1 procedure as specified by EN ISO 14956. Using this standard, it shall be proven that the total uncertainty of the results obtained from the AMS meets the specification for uncertainty stated in the applicable regulations. Such suitability testing has to be carried out under specific conditions by an independent third party on a specific testing site. A test institute shall perform all relevant tests on two identical AMS. These two AMS have to be tested in the laboratory and field.

At the time of purchasing of the AMS by AEL, no AMS vendors had yet conducted the QAL 1 suitability testing for N₂O and it was not known if any vendors were in the process of obtaining this. The chosen gas analyser MIR9000 from Environnement however, has passed the QAL1 suitability for measurements of NO_x and other gaseous emissions. In addition QAL1 tests for N₂O were successfully performed in 2007 by an independent 3rd party testing laboratory with EN ISO/IEC 17025 accreditation. The Environnement S.A. MIR9000 analyser was used during the baseline campaign. Before start of the first project campaign it was replaced by a ABB AO2040 Uras 14 NDIR analyser.

According to ABB’s own certificate, this analyser has an accuracy of better than 1% of range. This analyser has been certified¹ as meeting the requirements (QAL1) of the German emissions standards

¹ TÜV Süddeutschland Bau und Betrieb GmbH (Report number 170 608), March 2003

17th BImSchV and 13th BImSchV (waste incineration plants, large furnaces and others) for the components NO, CO and SO₂. At the time of commissioning of the AMS by AEL no AMS was available that had been certified according with EN 14181 QAL1 for N₂O measurements. However, TÜV SÜD has conducted and successfully completed the QAL1 tests² for the follow-up model of this analyser module within the same analyser series (ABB AO2040 Uras 26). Since there are no major technical differences between the two analyser models it can be assumed that the Analyser installed at the AEL No. 11 nitric acid plant meets the requirements of the QAL1 test in the same way as the follow-up model.

QAL2 and Standard Reference Measurements (SRM)

QAL2 is a procedure for the determination of the calibration function and its variability, and a test of the variability of the measured values of the AMS compared with the uncertainty given by legislation. The QAL2 tests are performed on suitable AMS that have been correctly installed and commissioned on-site (as opposed to QAL 1 which is conducted off-site). QAL 2 tests are to be performed at least every 5 years according to EN 14181 but also after major changes to the plant or changes or repairs to the AMS, which will influence the results obtained significantly.

A calibration function is established from the results of a number of parallel measurements performed with a Standard Reference Method (SRM). The variability of the measured values obtained with the AMS is then evaluated against the required uncertainty. According to EN 14181, both the QAL 2 procedures and the SRM need to be conducted by an independent “testing house” or laboratory which has to be accredited to EN ISO/IEC 17025.

A series of QAL2 specific reference measurements using a the SRM method as per EN 14181 for guidance has been carried out at the plant for both above mentioned N₂O analysers as well as for the stack gas flow meter by an accredited testing house (TÜV SÜD Industrie Service GmbH Germany; Müller-BBM GmbH, Germany) to ensure the AMS’ suitability, establish the calibration curve and test the variability of the measurements. The results of these SRM are available to the DOE as part of the verification process. The AMS calibration function as well as the total uncertainty of the AMS was determined. The results were applied in the calculation of EF_{BL} and EF_n.

An annual surveillance test (AST) is used between QAL2 tests to demonstrate that the AMS functions correctly, its performance remains valid and that the calibration function and variability derived during the QAL2 remains as previously determined.

According to the monitoring plan in the PDD it is not necessary to perform an AST by an accredited independent third party. Instead regular QAL3 procedures as periodic zero and span calibrations, checks of the analyser system and maintenance of the AMS are performed. However in addition to these calibrations, AEL decided to perform an AST test. For the N₂O measurement at 06/07/2010 an Annual Surveillance Tests (AST) has been successfully performed by an accredited testing house. The test was performed in accordance with EN14181. The AST test confirmed that the calibration function as determined during QAL2 is still valid and that the requirements for variability are fulfilled. At 22/ – 25/06/2011 a QAL 2 (including AST) was performed.

For the stack gas flow measurement at 06/ - 08/07/2010 a QAL2 test (including AST) has been successfully performed by an accredited testing house. The test was performed in accordance with EN14181. With the QAL2 test in 2010 a new QAL2 correction factor for stack gas flow was defined. At 22/ – 25/06/2011 an AST test was performed. The AST test confirmed that the calibration function as determined during QAL2 is still valid and that the requirements for variability are fulfilled.

8. AMS calibration and QA/QC procedures

AEL is certified according to ISO 9001 and 14001 standards for quality and environmental management respectively. The procedures for monitoring, regular calibrations and QA/QC are fully embedded into the procedures required by ISO 9001/14001 and documented in the applicable ISO handbooks. The South African Bureau of Standards (SABS) is the designated auditor for these standards at AEL. Therefore, all of the monitoring equipment is subjected to the regular “SABS testing loops” as part of the ISO 9001/14001 procedures.

² TÜV Süd Industrie Service GmbH, München (Report number 821029) June 2006

Calibration Gas

A certified N₂O Calibration gas (balance being N₂) with a precision of $\pm 2\%$ is used in the span calibrations.

Analyser Zero and Span Calibrations

According to the QAL 1 reports and manufacturers specifications it is recommended to perform a zero/span calibration every 7 days for the Environnement MIR 9000 analyser and once every three weeks for the ABB URAS 14 analyser, however AEL decided to do it twice per week in order to have a closer control over the instrument. For the zero calibration pure nitrogen is used, for the span calibration a certified calibration gas is used. The results of the calibrations are recorded according to the related CDM procedure.

Flow meter calibration procedures

The flow meter is calibrated once per year by external AST test according to EN 14181. In addition, the flow meter is calibrated at least once per year (the plant has to be shut down to conduct calibration) by the Instrument Department of AEL. The pressure transmitter is disconnected from the Annubar and the transmitter is then connected to an absolute pressure simulator that has been approved by the South Africa Bureau of Standards (SABS).

If the deviation exceeds 1% of range, then the pressure transmitter is recalibrated and the previous procedure repeated.

The Annubar itself does not need to be calibrated since it is a physical device which will not have drift. Therefore, it is sufficient to regularly inspect the physical condition of the Annubar. Therefore, the Annubar is taken out of the stack once per year for physical inspection.

The results of these calibration procedures are then recorded in the Calibration Procedure log sheet.




Figure: Monitoring Points for all relevant Parameters (NCSG, VSG, TSG, PSG, NAP, OT_h, OP_h, AFR

Training

Operations staff at the nitric acid plant who are responsible for the operation of the AMS and regular calibrations, visual and physical checks have been trained appropriately by the AMS vendors and AELs' own instrumentation engineers.

QAL 3

QAL3 is a procedure which is used to check drift and precision in order to demonstrate that the AMS is in control during its operation so that it continues to function within the required specifications for uncertainty.

This is achieved by conducting periodic zero and span checks on the AMS and then evaluating the results obtained using control charts. Zero and span adjustments or maintenance of the AMS, may be necessary depending on the results of this evaluation.

8.1 Data Acquisition System and Emergency Procedures

The analogue signal (4 to 20 mA) output from the Analyser and Flow meter are converted by the Programmable Logic Controller (PLC) into a digital signal which is then fed into the SCADA data acquisition and database system.

Each of AEL's two nitric acid plants has its own SCADA system on a dedicated PC near the respective plant itself. However, the two SCADA PCs are directly connected to each other and each of the PCs receives all of the measured data from the AMS and stores them. That way there is a constant redundancy of data acquisition and storage. In addition, the instrumentation engineer transfers the data at least once a week into AEL's main IT system as well as making a complete copy of that weeks data (2-second, hourly and daily averages) onto an external disc drive. That way there are already four copies of the original and unchanged data stored in four different locations. In addition, the hourly data are sent to N.serve on a regular basis (e. g. after each campaign) where they are also stored.

The SCADA system automatically produces comma separated files stored in Microsoft Excel of the 2-second values and it also automatically produces hourly and daily average values for each of the measured parameters. The hourly averages are the basis of the analysis of the data for the purpose of the calculation of the emissions factors for the baseline and for the project campaigns. These are then extracted and converted into excel files which can then be imported into the N.serve Database Management System (N.DBMS).

N.serve Database Management System (N.DBMS)

All data necessary for the monitoring and verification procedures related to the project activity are transferred from the nitric acid plant's data acquisition system into N.serve's dedicated relational database management system ("N.DBMS") based on Microsoft Access 2002. Database management systems are designed for a structured storage of large amounts of data providing for minimum redundancy and maximum flexibility to allow best practice data analysis.

The N.DBMS is designed to conduct all the calculation steps required by the methodology in order to derive the baseline and project emissions factors and to calculate the amount of emission reductions resulting from the project activity.

The use of the N.DBMS system is described in the PDD and therefore part of the validated monitoring plan. For the purpose of plausibility checks and for transparency reasons all calculations are also provided in an EXCEL calculation sheet. This EXCEL calculation sheet will be submitted in addition to the N.DBMS documentation sheet along with the request for issuance to allow easy crosschecks and recalculations.

SECTION D. Data and parameters

D.1. Data and parameters determined at registration and not monitored during the monitoring period, including default values and factors

Data / Parameter:	B.1 NCSG_{BC}
Data unit:	mg/Nm³
Description:	N ₂ O concentration in the stack gas during the baseline campaign.
Source of data used:	NDIR N ₂ O gas analyser (Environnement S.A. MIR 9000)
Value(s) :	Value applicable for regular project campaigns exceeding CL _{normal} or CL _{BL} : 1,630 Value applicable for Project Campaign 8: 1,598.97
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations
Additional comment:	

Data / Parameter:	B.2 VSG_{BC}
Data unit:	Nm³/h
Description:	Normal gas volume flow rate of the stack gas during the baseline campaign.
Source of data used:	Gas Volume Flow meter, Emerson Rosemount Annubar® Model 485
Value(s) :	72,468
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.3 BE_{BC}
Data unit:	tN₂O
Description:	Total N ₂ O mass flow during baseline campaign
Source of data used:	Calculation from measured data.
Value(s) :	Value applicable for regular project campaigns exceeding CL _{normal} or CL _{BL} : 651.983 Value applicable for Project Campaign 8: 639.561
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.4 OH_{BC}
Data unit:	hours
Description:	Operating hours
Source of data used:	Production log
Value(s) :	4,950
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.5 NAP_{BC}
Data unit:	tHNO₃
Description:	Metric tonnes of 100% concentrated nitric acid produced during the baseline campaign.
Source of data used:	Coriolis mass flow meter measurements
Value(s) :	134,700
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	The nitric acid flow meter is subject of external calibration procedures every 3 years.

Data / Parameter:	B.6 TSG
Data unit:	°C
Description:	Temperature in the stack gas
Source of data used:	Stack temperature probe situated directly next to the volume flow meter.
Value(s) :	Not applicable
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	

Data / Parameter:	B.7 PSG
Data unit:	Pa
Description:	Pressure in the stack
Source of data used:	Stack temperature probe situated directly next to the volume flow meter.
Value(s) :	Not applicable
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	The PSG result is automatically applied for calculating VSG at standard conditions

Data / Parameter:	B.8 EF_{BL}
Data unit:	tN₂O / tHNO₃
Description:	Emissions factor for baseline period
Source of data used:	Calculated from measured data (tons of N ₂ O emitted / tons of nitric acid produced)
Value(s) :	Value applicable for regular project campaigns exceeding CL _{normal} or CL _{BL} : 0.004647 Value applicable for Project Campaign 8 : 0.004559
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.9 UNC
Data unit:	%
Description:	Calculated overall uncertainty of the Automated Monitoring System (AMS)
Source of data used:	Engineering reports and calculations conducted by the manufacturer of the

	components of the AMS.
Value(s) :	3,99%
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline / Project emission calculations.
Additional comment:	None

Data / Parameter:	B.10 AFR
Data unit:	tNH₃/h
Description:	Mean Ammonia gas flow rate to the ammonia oxidation reactor
Source of data used:	Orifice plate
Value(s) :	Not applicable, monitored data of AFR will be used to determine if plant was operating outside of AFR _{max} during the baseline campaign.
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.11 AFR_{max}
Data unit:	tNH₃/h
Description:	Maximum Ammonia gas flow rate to the ammonia oxidation reactor
Source of data used:	AFR data
Value(s) :	9.094
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.12 AIFR
Data unit:	% v/v
Description:	Mean Ammonia to air ratio into the ammonia oxidation reactor
Source of data used:	Measurements of AFR and primary air flow rates (measured by orifice plate).
Value(s) :	Not applicable, monitored data of AIFR will be used to determine if plant was operating outside of AIFR _{max} during the baseline campaign.
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.13 CL_{BL}
Data unit:	tHNO₃
Description:	Length of the baseline campaign measured in metric tonnes of 100% concentrated nitric acid produced during that baseline campaign.
Source of data used:	NAP _{BC}
Value(s) :	134,700
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.14 CL_{normal}
Data unit:	tHNO₃
Description:	Average length of the historic campaigns measured in metric tonnes of 100% concentrated nitric acid produced during the historic campaigns.
Source of data used:	Coriolis Flow meter as described in NAP.
Value(s) :	127,302.4
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline / Project emission calculations.
Additional comment:	None

Data / Parameter:	B. 15 AIFR_{max}
Data unit:	% v/v
Description:	Maximum Ammonia to air ratio into the ammonia oxidation reactor.
Source of data used:	Plant operating manual
Value(s) :	11.5
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.16 OT_h
Data unit:	°C
Description:	Oxidation temperature for each hour during the baseline campaign
Source of data used:	Monitoring results of three thermocouples inside the ammonia oxidation reactor and recorded by the data acquisition system.
Value(s) :	Not applicable
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.17 OT_{normal}
Data unit:	°C (min and max)
Description:	Normal range operating temperature
Source of data used:	Design specifications and operating manual of the No. 11 nitric acid plant (Technical Manual (TM4 June 1977, p. 250) ³ .
Value(s) :	820 to 905
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.18 OP_h
Data unit:	Pa (gauge)
Description:	Oxidation Pressure for each hour during the baseline campaign

³ Copies of the technical plant manuals can be provided to the DOE upon request.

Source of data used:	Design specifications and operating manual of the No. 11 nitric acid plant (Drawing No. D31 113-4, Sheet 2, December 1977; Operating Instructions No. M69.0300.2008, 1978; No 11 Plant Understanding, p. 10).
Value(s) :	Not applicable.
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	The uncertainty of the pressure sensor is 0.125% according to the vendor. However, since the measurement uncertainty during the baseline campaign and during the project campaigns is the same, the two data series will always be comparable.

Data / Parameter:	B.19 OP_{normal}
Data unit:	kPa (gauge) min and max
Description:	Normal range of operating pressure in the ammonia oxidation reactor.
Source of data used:	Plant operating manual
Value(s) :	365 – 450
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.20 GS_{normal}
Data unit:	Name of Supplier
Description:	Gauze supplier for the operating condition (i.e. historic) campaigns
Source of data used:	Monitored / Invoices
Value(s) :	W.C. Heraeus
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.21 GS_{BL}
Data unit:	Name of Supplier
Description:	Gauze supplier for the baseline condition campaign
Source of data used:	Monitored / Invoices
Value(s) :	W.C. Heraeus
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline emission calculations.
Additional comment:	None

Data / Parameter:	B.23 GC_{normal}
Data unit:	%
Description:	Gauze composition during the historic operating campaigns expressed as percentage by weight of the precious metals Platinum, Rhodium and, if applicable, Palladium comprising the Ammonia Oxidation Catalyst gauzes.
Source of data used:	Monitored / Gauze supplier invoices
Value(s) :	Platinum (Pt) 56.5%; Rhodium (Rh) 3.8%; Palladium (Pd) 39.7%
Indicate what the data are used for (Baseline/	Baseline emission calculations.

Project/ Leakage emission calculations)					
Additional comment:	Record of Gauze compositions installed during the historic campaigns ⁴ :				
	Campaign	Gauze Supplier	Gauze Composition		
			Pt (%)	Rh (%)	Pd (%)
	C10	Heraeus	58.3	3.9	37.9
	C12	Heraeus	56.1	3.8	40.1
	C13	Heraeus	56.4	3.8	39.8
	C14	Heraeus	56.1	3.8	40.1
	C15	Heraeus	55.4	3.8	40.8
	Average		56.5	3.8	39.7

Data / Parameter:	B.24 GC_{BL}
Data unit:	%
Description:	Gauze composition during the baseline campaign expressed as percentage by weight of the precious metals Platinum, Rhodium and, if applicable, Palladium comprising the Ammonia Oxidation Catalyst gauzes.
Source of data used:	Monitored / Gauze supplier invoices
Value(s) :	Platinum (Pt) 56%; Rhodium (Rh) 3.8%; Palladium (Pd) 40.2%
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline / Project emission calculations.
Additional comment:	None

Data / Parameter:	B.26 EF_{reg}
Data unit:	tN ₂ O/tHNO ₃
Description:	Emissions cap for N ₂ O from nitric acid production set by government regulation
Source of data used:	Department of Environmental Affairs and Tourism
Value(s) :	None
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Baseline / Project emission calculations.
Additional comment:	None.

D.2. Data and parameters monitored

Data / Parameter:	NCSG
Data unit:	mg / Nm³ (convertible from ppmv, if required)
Description:	N ₂ O concentration in the stack gas during each project campaign.
Measured /Calculated /Default:	Measured/Calculated - every 2 sec. used for calculation of campaign mean (average, after exclusion of extreme values and outliers)
Source of data:	NDIR N ₂ O gas analyser (ABB AO2040 Uras-14)
Value(s) of monitored parameter:	Project Campaign 8: 734.30
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.

⁴ The figures shown here are rounded figures. More exact figures are commercially sensitive information but can be inspected by the DOE during the site visit and can be made available to the CDM EB upon request.

Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	<p>Type: N₂O gas analyser, nondispersive infrared sensor (NDIR) spectrometry</p> <p>Measurement uncertainty (for N₂O): 2.69% (according to QAL2)</p> <p>Serial Number: <i>Instrument number 3.346854.7</i></p> <p>Calibration frequency:</p> <ul style="list-style-type: none"> - <i>External calibration: QAL2 every 5 years;</i> - <i>External calibration: AST every year;</i> - <i>Internal calibration: twice per week manual calibration with test gas.</i> <p>Bi-weekly Zero and span check and calibration in case of deviation >1% of range of analyzer against zero gas and certified calibration gas cylinder (internal calibration by AEL) Documentation in form of calibration reports and Shewart charts.</p> <p>First calibration for monitoring period: 03/03/2011</p> <p>During the monitoring period: calibrations performed twice per week</p> <p>Last calibration for monitoring period: 04/08/2011</p> <p>Date of last external calibration:</p> <p style="text-align: right;"><i>AST Test – 06/07/2010 valid until 05/07/2011</i></p> <p style="text-align: right;"><i>QAL2 Test – 22/- 25/06/2011 valid until 21/06/2016</i></p>
Measuring/ Reading/ Recording frequency:	Continuously (every 2 seconds)
Calculation method (if applicable):	<p>NCSG is continuously monitored with an NDIR gas analyser and monitoring results are taken and recorded for every two seconds of plant operation. Hourly means for NCSG are derived by the data acquisition system. NCSG data taken during times when the plant was out of operation were eliminated. Also readings that were taken during malfunction of the monitoring system were eliminated. The remaining hourly average values were subjected to the following statistical analysis:</p> <ol style="list-style-type: none"> a) Calculate the sample mean (x) b) Calculate the sample standard deviation (s) c) Calculate the 95% confidence interval (equal to 1.96 times the standard deviation) d) Eliminate all data that lie outside the 95% confidence interval e) Calculate the new sample mean from the remaining NCSG values <p>During the QAL2 reference measurements it was determined that the analyser consistently overestimates the N₂O concentration in the stack. As a result from the QAL2 calibration curve, it was determined that a correction factor of 0.99 will have to be applied to all NCSG measurements. Therefore, the result of the above statistical analysis, i.e. the mean NCSG value will be multiplied by 0.99 before going into the calculation of PE_n.</p>
QA/QC procedures applied:	<p>Bi-weekly Zero and Span check and calibration performed by trained AEL personnel. Documentation in form of calibration reports and Shewart charts</p> <p>every 5 years QAL2 test (including AST) according to EN 14181 (External by qualified institute)</p> <p>yearly AST test according to EN 14181 (External by qualified</p>

	institute)
Data / Parameter:	VSG
Data unit:	Nm³/h
Description:	Normal gas volume flow rate of the stack gas during each project campaign.
Measured /Calculated /Default:	Measured/Calculated - every 2 sec. used for calculation of campaign mean (average, after exclusion of extreme values and outliers)
Source of data:	Gas Volume Flow meter, Emerson Rosemount Annubar® Model 485
Value(s) of monitored parameter:	Project Campaign 8: 80,653
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	<p>Type: Tail gas flow by differential pressure principle Overall measurement accuracy: 2.84% (<i>per QAL 2 report</i>) Combined uncertainty for the normalized stack gas flow at standard conditions: 2.96% (<i>per QAL 2 report</i>)</p> <p>Serial Number: <i>instrument number N/A</i> Calibration frequency: - External calibration: <i>QAL2 every 5 years;</i> - External calibration: <i>AST every year;</i> - Internal calibrations: <i>after each campaign (usually every 7 month)</i></p> <p>Date of last external calibration: <i>QAL2 Test (including AST) – 06/07/2010 – 08/07/2010 valid until 05/07/2015</i> <i>AST test 22/06/2011 – 25/06/2011 valid until 21/06/2012</i> Date of internal calibrations: <i>09/03/2011, 10/08/2011</i></p>
Measuring/ Reading/ Recording frequency:	Continuously (every 2 seconds).
Calculation method (if applicable):	<p>VSG is continuously monitored with a flow meter and monitoring results are taken and recorded for every two seconds of plant operation. Hourly means for VSG are derived by the data acquisition system. Temperature and pressure is also continuously measured in the stack and the VSG values subsequently adjusted to derive the VSG at normal conditions (i.e. standard pressure and temperature).</p> <p>VSG data taken during times when the plant was out of operation were eliminated.</p> <p>The resulting hourly average VSG values are now expressed in Nm³/h as required by AM0034 and where subsequently subjected to the following statistical analysis:</p> <ol style="list-style-type: none"> Calculate the sample mean (x) Calculate the sample standard deviation (s) Calculate the 95% confidence interval (equal to 1.96 times the standard deviation) Eliminate all data that lie outside the 95% confidence interval Calculate the new sample mean from the remaining VSG values

	As a result from the latest QAL2 calibration curve, it was determined that a correction factor of 0.96 will have to be applied to all VSG measurements. Therefore, the result of the above statistical analysis, i.e. the mean VSG value will be multiplied by 0.96 before going into the calculation of PE_n .
QA/QC procedures applied:	<p>internal calibration at least once per year usually every 7 month after each campaign (the plant has to be shut down to conduct calibration) by the Instrument Department of AEL.</p> <p>every 5 years QAL2 test (including AST) according to EN 14181 (External by qualified institute)</p> <p>yearly AST test according to EN 14181 (External by qualified institute)</p>

Data / Parameter:	PE_n
Data unit:	tN_2O
Description:	Total mass N_2O emissions in each project campaign.
Measured /Calculated /Default:	Calculated.
Source of data:	Calculated from measured values.
Value(s) of monitored parameter:	Project Campaign 8: 170.94
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Not applicable.
Measuring/ Reading/ Recording frequency:	Not applicable.
Calculation method (if applicable):	$PE_n = VSG * NCSG * 10^{-9} * OH$ A special correction function is applied to the results for NCSG and VSG values. These correction factors were determined during the QAL2 test according to EN 14181. QAL2 correction functions are applied in the calculation
QA/QC procedures applied:	Not applicable.

Data / Parameter:	OH_n
Data unit:	Hours
Description:	Total operating hours during each project campaign
Measured /Calculated /Default:	Measured.
Source of data:	Process Control System.
Value(s) of monitored parameter:	Project Campaign 8: 3,037
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.

calculations)	
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Not applicable.
Measuring/ Reading/ Recording frequency:	The total operating hours are logged continuously.
Calculation method (if applicable):	Not applicable.
QA/QC procedures applied:	The production logging process is subject to ISO 9001 procedures

Data / Parameter:	NAP
Data unit:	tHNO₃
Description:	Metric tonnes of 100% concentrated nitric acid during each project campaign.
Measured /Calculated /Default:	Measured / Calculated.
Source of data:	Coriolis mass flow meter measurements.
Value(s) of monitored parameter:	Project Campaign 8: 86,488
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Emerson CMF 300, Coriolis mass flow meter Overall measurement accuracy: $\leq 0.1\%$ Serial Number: 12038740 Calibration frequency: once every 3 years (although the calibration is valid for 3 years, it is done more frequently) Date of last calibrations: <i>15/10/2010 valid until 14/10/2013;</i> <i>09/03/2011 valid until 08/03/2014</i>
Measuring/ Reading/ Recording frequency:	Continuously
Calculation method (if applicable):	NAP is determined in the following way: NAP is determined by a mass flow meter according to the following procedures: The density and temperature as measured by the mass flow meter is used to calculate the concentration of the nitric acid produced. This value is then used to convert the total mass flow to 100% nitric acid produced. The correct measurement of acid concentration is checked by manual tests.
QA/QC procedures applied:	Subjected to complete SABS testing loops as part of the ISO 9001/14001 procedures. The mass flow meter is calibrated in regular intervals.

Data / Parameter:	TSG
Data unit:	°C
Description:	Temperature in the stack gas
Measured /Calculated	Measured.

/Default:	
Source of data:	Stack temperature probe situated directly next to the volume flow meter;
Value(s) of monitored parameter:	Not applicable
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	<p>Type: Rosemont thermocouple, PT100_385 3-wire RTD Overall measurement accuracy: 2.55% (per QAL2 report) Serial Number: <i>instrument number N/A</i> Calibration frequency: - <i>External calibration: QAL2 every 5 years;</i> - <i>External calibration: AST every year;</i> - <i>Internal calibrations: after each campaign (usually every 7 month)</i></p> <p>Date of last external calibration: <i>QAL2 Test (including AST) – 06/07/2010 – 08/07/2010 valid until 05/07/2015</i> <i>AST Test 22/06/2011 -25/06/2011 valid until 21/06/2012</i> <i>Date of internal calibrations: 09.03.2011, 10.08.2011</i></p>
Measuring/ Reading/ Recording frequency:	Continuously (every 2 seconds)
Calculation method (if applicable):	AM0034 requires the determination of gas volume flow at normal conditions in the stack. In order to calculate from the measured VSG values to VSG at normal conditions, the actual temperature in the stack is measured by a temperature probe as part of the flow meter.
QA/QC procedures applied:	<p>internal calibration at least once per year usually every 7 month after each campaign (the plant has to be shut down to conduct calibration) by the Instrument Department of AEL.</p> <p>every 5 years QAL2 test (including AST) according to EN 14181 (External by qualified institute)</p> <p>yearly AST test according to EN 14181 (External by qualified institute)</p>

Data / Parameter:	PSG
Data unit:	Pa (absolute)
Description:	Pressure in the stack
Measured /Calculated /Default:	Measured.
Source of data:	Stack pressure probe situated directly next to flow meter
Value(s) of monitored parameter:	Not applicable, directly used for normalization of tail gas volume flow measurement.
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type,	Manufacturer: Rosemont

accuracy class, serial number, calibration frequency, date of last calibration, validity)	<p>Type: 3051TA1A2B21BB4I1M5Q4</p> <p>Overall measurement accuracy: 0.7 % (per QAL2 report)Serial Number: <i>instrument number N/A</i></p> <p>Calibration frequency:</p> <ul style="list-style-type: none"> - <i>External calibration: QAL2 every 5 years;</i> - <i>External calibration: AST every year;</i> - <i>Internal calibrations: after each campaign (usually every 7 month)</i> <p>Date of last external calibration:</p> <p><i>QAL2 Test (including AST) – 06/07/2010 – 08/07/2010 valid until 05/07/2015</i></p> <p><i>AST Test 22/06/2011 -25/06/2011 valid until 21/06/2012</i></p> <p>Date of internal calibrations: <i>09/03/2011, 10/08/2011</i></p>
Measuring/ Reading/ Recording frequency:	Continuously (every 2 seconds).
Calculation method (if applicable):	AM0034 requires the determination of gas volume flow at normal conditions in the stack. In order to calculate from the measured VSG values to VSG at normal conditions, the actual pressure in the stack has to be determined and applied to each hourly mean VSG value. The measurements are taken continuously by a pressure probe inside the stack very close to the stack gas volume flow meter.
QA/QC procedures applied:	<p>internal calibration at least once per year usually every 7 month after each campaign (the plant has to be shut down to conduct calibration) by the Instrument Department of AEL.</p> <p>every 5 years QAL2 test (including AST) according to EN 14181 (External by qualified institute)</p> <p>yearly AST test according to EN 14181 (External by qualified institute)</p>

Data / Parameter:	EF_n
Data unit:	tN₂O/tHNO₃
Description:	Emissions factor for campaign n.
Measured /Calculated /Default:	Calculated.
Source of data:	Calculation from total mass N ₂ O emissions of campaign n (PE _n) and total nitric acid production (NAP _n)
Value(s) of monitored parameter:	Project Campaign 8: 0.001976
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Not applicable.
Measuring/ Reading/ Recording frequency:	Not applicable.

Calculation method (if applicable):	The campaign specific emissions factor for each campaign during the project's crediting period is calculated by dividing the total mass of N ₂ O emissions during that campaign by the total production of 100% concentrated nitric acid during that same campaign. For campaign <i>n</i> the campaign specific emission factor is: $EF_n = PE_n / NAP_n$
QA/QC procedures applied:	Not applicable.

Data / Parameter:	EF_{ma,n}
Data unit:	tN ₂ O/tHNO ₃
Description:	Moving average emissions factor derived over time from campaign specific emissions factors.
Measured /Calculated /Default:	Calculated.
Source of data:	Calculation from campaign specific emissions factors (EF _n)
Value(s) of monitored parameter:	Project Campaign 8: 0.000985
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Not applicable.
Measuring/ Reading/ Recording frequency:	Not applicable.
Calculation method (if applicable):	In order to take into account possible long-term emissions trends over the duration of the project activity and to take a conservative approach the moving average emission factor is determined as follows: $EF_{ma,n} = (EF_1 + EF_2 + \dots + EF_n) / n$ This process is repeated for each campaign such that a moving average, EF _{ma,n} is established over time, becoming more representative and precise with each additional campaign.
QA/QC procedures applied:	Not applicable.

Data / Parameter:	EF_p
Data unit:	tN ₂ O/tHNO ₃
Description:	Emissions factor used for the specific campaign <i>n</i> to determine the emission reductions of that campaign
Measured /Calculated /Default:	Calculated.
Source of data:	Calculation of EF _n and EF _{ma,n} .
Value(s) of monitored parameter:	Project Campaign 8: 0.001976
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last	Not applicable.

calibration, validity)	
Measuring/ Reading/ Recording frequency:	Not applicable.
Calculation method (if applicable):	To calculate the total emission reductions achieved in a campaign, the higher of the two values $EF_{ma,n}$ and EF_n shall be applied as the emission factor relevant for the particular campaign to be used to calculate emissions reductions (EF_P). Thus: If $EF_{ma,n} > EF_n$ then $EF_P = EF_{ma,n}$ If $EF_{ma,n} < EF_n$ then $EF_P = EF_n$
QA/QC procedures applied:	Not applicable.

Data / Parameter:	EF_{min}
Data unit:	$tN_2O/tHNO_3$
Description:	EF_{min} is equal to the lowest EF_n observed during the first 10 campaigns of the project crediting period.
Measured /Calculated /Default:	Calculated.
Source of data:	Calculations from EF_n
Value(s) of monitored parameter:	Not applicable – will be determined after 10 project campaigns
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Not applicable.
Measuring/ Reading/ Recording frequency:	Not applicable.
Calculation method (if applicable):	A campaign-specific emissions factor shall be used to cap any potential long-term trend towards decreasing N_2O emissions that may result from a potential built up of platinum deposits. After the first ten campaigns of the crediting period of the project, the lowest EF_n observed during those campaigns will be adopted as a minimum (EF_{min}). If any of the later project campaigns results in a EF_n that is lower than EF_{min} , the calculation of the emission reductions for that particular campaign shall use EF_{min} and not EF_n .
QA/QC procedures applied:	Not applicable.

Data / Parameter:	CL_n
Data unit:	$tHNO_3$
Description:	Length of each project campaign measured in metric tonnes of 100% concentrated nitric acid produced during that campaign.
Measured /Calculated /Default:	Measured.
Source of data:	NAP
Value(s) of monitored parameter:	Project Campaign 8: 86,488
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Project emission calculations.

Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	See comments for NAP above
Measuring/ Reading/ Recording frequency:	See comments for NAP above
Calculation method (if applicable):	In accordance with AM0034 the project length (CL_n) has to be compared to the established average historic campaign length (CL_{normal}); and if the length of each individual project campaign CL_n is longer than or equal to the average historic campaign length CL_{normal} , then all N_2O values measured during the baseline campaign can be used for the calculation of EF (subject to the elimination of data from the operational parameters analysis). If $CL_n < CL_{normal}$, recalculate EF_{BL} by eliminating those N_2O values that were obtained during the production of tonnes of nitric acid beyond the CL_n (i.e. the last tonnes produced) from the calculation of EF_n .
QA/QC procedures applied:	See comments for NAP above

Data / Parameter:	OP_h
Data unit:	Pa (gauge)
Description:	Oxidation Pressure for each hour
Measured /Calculated /Default:	Measured.
Source of data:	Discharge of the air compressor before the ammonia to air mixer
Value(s) of monitored parameter:	Not applicable. Used to determine when plant is operating outside of permitted range during baseline campaign or if the plant is out of operation.
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Not applicable.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Supplier: Yokogawa Type: Pressure Tx Measurement uncertainty: 1.7 % (per AEL calibration requirements) Serial Number: F576FB671708 Installation location: Compressor floor Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 08/03/2011, 09/08/2011
Measuring/ Reading/ Recording frequency:	The measurement results are taken by the data acquisition and evaluation system. The system directly calculates hourly averages.
Calculation method (if applicable):	See above
QA/QC procedures applied:	Subject to ISO 9001/14001 procedures. Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 08/03/2011, 09/08/2011

Data / Parameter:	OT_h
Data unit:	°C
Description:	Oxidation temperature in the ammonia oxidation reactor (AOR) for each hour.
Measured /Calculated	Measured.

/Default:	
Source of data:	Monitoring results of three thermocouples inside the ammonia oxidation reactor and recorded by the data acquisition system.
Value(s) of monitored parameter:	Not applicable. Used to determine when plant is operating outside of permitted range during baseline campaign or if the plant is out of operation.
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Not applicable.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Supplier: Thermocouple Products Type: K310 S/steel Thermocouple Measurement uncertainty: 1 % (per AEL calibration requirements) Serial Number: TP3285-3290 Installation location: reactor Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 09/03/2011, 08/08/2011
Measuring/ Reading/ Recording frequency:	The measurement results are taken by the data acquisition and evaluation system. The system directly calculates hourly averages.
Calculation method (if applicable):	See above
QA/QC procedures applied:	Subject to ISO 9001/14001 procedures. Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 09/03/2011, 08/08/2011

Data / Parameter:	AFR
Data unit:	tNH₃/h
Description:	Ammonia gas flow rate to the ammonia oxidation reactor.
Measured /Calculated /Default:	Measured.
Source of data:	Orifice plate
Value(s) of monitored parameter:	Not applicable, monitored data of AFR will be used to determine if the plant operating outside of AFR_{max} during the baseline campaign or for plausibility checks
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Not applicable.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Supplier: Yokogawa Type: D.P Transmitter Measurement accuracy: 1.25 % (per AEL calibration requirements) Serial Number: F570FD073708 Installation location: compressor floor Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 08/03/2011, 09/08/2011
Measuring/ Reading/ Recording frequency:	The measurement results are taken by the data acquisition and evaluation system. The system directly calculates hourly averages.
Calculation method (if applicable):	See above
QA/QC procedures applied:	Subject to ISO 9001/14001 procedures.

	Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 08/03/2011, 09/08/2011
--	---

Data / Parameter:	AIFR
Data unit:	% v/v
Description:	Ammonia to air ratio into the ammonia oxidation reactor
Measured /Calculated /Default:	Calculated (primary air flow measured as basis for AIFR).
Source of data:	Calculation for each hour of plant operation based on measurements of AFR and primary air flow rates.
Value(s) of monitored parameter:	Not applicable, monitored data of AIFR will be used to determine if the plant operating outside of AIFR_{max} during the baseline campaign or for plausibility checks
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Not applicable.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Primary Air flow rate: Supplier: Yokagawa Type: D.P Transmitter Measurement accuracy: 1.66 % (per AEL calibration requirements) Serial Number: F570FD 069708 Installation location: compressor floor Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 08/03/2011, 09/08/2011
Measuring/ Reading/ Recording frequency:	The measurement results are taken by the data acquisition and evaluation system. The system directly calculates hourly averages.
Calculation method (if applicable):	AIFR is calculated from AFR and the primary air flow to the ammonia oxidation reactor. The airflow rate is measured by orifice plate and expressed in kg/hr and is then converted to Nm ³ /h, which is used in the ratio calculation.
QA/QC procedures applied:	Subject to ISO 9001/14001 procedures. Calibration frequency: Once every seven months. (only during plant shutdown between campaigns) Date of last calibration: 03/08/2010, 08/03/2011, 09/08/2011

Data / Parameter:	GS_{project}
Data unit:	Name of Supplier
Description:	Gauze supplier for the project campaign
Measured /Calculated /Default:	Not applicable.
Source of data:	Monitored / Invoices
Value(s) of monitored parameter:	W.C. Heraeus
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Not applicable.
Monitoring equipment (type, accuracy class, serial	Not applicable.

number, calibration frequency, date of last calibration, validity)	
Measuring/ Reading/ Recording frequency:	Not applicable.
Calculation method (if applicable):	Not applicable.
QA/QC procedures applied:	Not applicable.

Data / Parameter:	GC_{project}
Data unit:	%
Description:	Gauze composition during the project campaign expressed as % by weight of the precious metals Platinum, Rhodium and, if applicable, Palladium comprising the Ammonia Oxidation Catalyst gauzes.
Measured /Calculated /Default:	Not applicable.
Source of data:	Monitored / Gauze supplier invoices
Value(s) of monitored parameter:	Platinum (Pt) 55.9%; Rhodium (Rh) 3.8%, Palladium (Pd) 40.3%
Indicate what the data are used for (Baseline/ Project/ Leakage emission calculations)	Not applicable.
Monitoring equipment (type, accuracy class, serial number, calibration frequency, date of last calibration, validity)	Not applicable.
Measuring/ Reading/ Recording frequency:	Not applicable.
Calculation method (if applicable):	Not applicable.
QA/QC procedures applied:	Not applicable.

SECTION E. Emission reductions calculation

E.1. Baseline emissions calculation

>>

N.serve Database Management System (N.DBMS)

All data necessary for the monitoring and verification procedures related to the project activity are transferred from the nitric acid plant's data acquisition system into N.serve's dedicated relational database management system ("N.DBMS") based on Microsoft Access 2002. Database management systems are designed for a structured storage of large amounts of data providing for minimum redundancy and maximum flexibility to allow best practice data analysis.

The N.DBMS is designed to conduct all the calculation steps required by the methodology in order to derive the baseline and project emissions factors and to calculate the amount of emission reductions resulting from the project activity.

The use of the N.DBMS system is described in the PDD and therefore part of the validated monitoring plan. For the purpose of plausibility checks and for transparency reasons all calculations are also provided in an EXCEL calculation sheet. This EXCEL calculation sheet will be submitted in addition to the N.DBMS documentation sheet along with the request for issuance to allow easy crosschecks and recalculations.

The monitoring results for Oxidation Temperature and Pressure have been routinely discarded in the past and are therefore not available to establish the normal range. As a substitute, the technical manuals of the No. 11 nitric acid plant were used to derive these normal ranges. See section D.1. for details.

Historic data of daily NH_3 consumption was used to determine the range of AFR for the five historic campaigns (excluding abnormal campaigns). After removing the top 2.5 percentile values the maximum daily flow rate was derived which was then converted into an hourly Ammonia flow rate, which was used to determine AIFR.

The following data was established from the above mentioned sources as permitted operating conditions:

Oxidation temperature (min – max): 820 °C – 905 °C

Oxidation pressure (min – max): 365,000 Pa – 450,000 Pa

Maximum ammonia flow rate : 9.094 t/h

Maximum ammonia to air ratio: 0,115 or 11,5 %

$\text{CL}_{\text{normal}}$: 127,302.4 t HNO_3

As Baseline the campaign C16 (20/07/2006 – 18/02/2007) was selected.

Analysis of Baseline campaign data

As the baseline campaign for AEL No. 11 the campaign C16 was used. The baseline campaign was in operation in the period 20/07/2006 – 18/02/2007. The baseline monitoring data, baseline calculation and baseline results were determined during the first verification and were verified by the DOE during the first verification.

The results are as follows:

NCSG_{BL}	mg/Nm ³	1,630.03
QAL2 NCSG		1.104
VSG_{BL}	Nm ³ /h	72,468
QAL2 VSG		1.01
OH_{BL}	h	4,950
NAP_{BL}	t HNO_3	134,700

BE	t N ₂ O	651.98
UNC		3.99
EF_{BL}	kg N₂O/t HNO₃	4.647

Adjustment of Baseline Emission Factor if $CL_n < CL_{normal}$

If the length of an individual project campaign CL_n is longer than or equal to the average historic campaign length CL_{normal} , then all N₂O values measured during the baseline campaign can be used for the calculation of EF_{BL}. If $CL_n < CL_{normal}$, EF_{BL} has to be recalculated by eliminating those N₂O values that were obtained during the production of tonnes of nitric acid beyond the CL_n (i.e. the last tonnes produced) from the calculation of EF_{BL}.

New calculation of Baseline emissions factor due to $CL_n < CL_{BL}$

Since for the project campaign 8 (PC8) $CL_n < CL_{BL}$, EF_{BL} is recalculated by eliminating those N₂O values that were obtained during the production of tonnes of nitric acid beyond the CL_{BL} (i.e. the last tonnes produced) from the calculation of EF_{BL}.

		Project campaign 8
NCSG _{BL}	mg/Nm ³	1,598.97
QAL2 NCSG		1.104
VSG _{BL}	Nm ³ /h	72,468
QAL2 VSG		1.01
OH _{BL}	h	4,950
NAP _{BL}	t HNO ₃	134,700
BE	t N ₂ O	639.561
UNC		3.99
EF_{BL}	kg N₂O/t HNO₃	4.559

As a result of this recalculation the new EF_{BL} to be applied for project campaign 8/ (PC8) is 4.559 kg N₂O /t HNO₃

Adjustment of Baseline emissions factor due to EF_{reg}

Should N₂O emissions regulations that apply to nitric acid plants be introduced in the host country or jurisdiction covering the location of the project activity, such regulations shall be compared to the calculated baseline emission factor for the project (EF_{BL}). If the regulatory limit is lower than the baseline factor determined for the project, the regulatory limit shall serve as the new baseline emission factor, that is:

if $EF_{BL} > EF_{reg}$,

then the baseline N₂O emission factor shall be EF_{reg} for all calculations.

where:

Variable Definition

EF_{BL} Baseline emissions factor (tN₂O/tHNO₃)

EF_{reg} Emissions level set by newly introduced policies or regulations (tN₂O/tHNO₃).

Such EF_{reg} shall be determined according to the nature of the regulation (e.g. in terms of absolute emission, by-product rate, concentration in stack gas), as described in the approved methodology AM0028.

There is currently no N_2O regulation for nitric acid plants in South Africa therefore no adjustment of the Baseline emissions factor EF_{BL} is applicable.

E.2. Project emissions calculation

>>

Project emissions are calculated according to the following formula:

$$PE_n = VSG * NCSG * 10^{-9} * OH$$

Variable	Definition
VSG	Mean stack gas volume flow rate for the project campaign (m ³ /h)
NCSG	Mean concentration of N_2O in the stack gas for the project campaign (mg N_2O /m ³)
PE_n	Total N_2O emissions of the n th project campaign (t N_2O)
OH	Is the number of hours of operation in the specific monitoring period (h)

Based on the total N_2O emissions of each project campaign the specific project campaign emission factor is calculated as:

$$EF_n = PE_n / NAP_n$$

Where:

Variable	Definition
EF_n	Project Emission Factor for n th project campaign (kg N_2O /t HNO_3)
PE_n	Total N_2O emissions of the n th project campaign (t N_2O or kg N_2O)
NAP_n	Campaign length of the n th project campaign (t HNO_3)

Before calculation of the Project Emissions (PE) the same statistical analysis as for the calculation of the baseline emission factor (EF_{BL}) is applied to the monitoring raw data (hourly average values) of each project campaign.

The respective correction functions for NCSG and VSG as determined during the relevant QAL2 test are applied within the calculation.

Analysis of Project campaign data

Query 1 (Raw data): Analysis of the raw campaign data

This set of data shows a summary of the collected raw data for both complete project campaigns.

N.DBMS Project Campaign Calculation Project: AEL No. 11, Johannesburg, South Africa Campaign: C 24 24.03.11 - 06.08.11									
Project campaign 8 Query 1: Without parameter limits 148									
Parameter	OH	AFR	AIFR	Oph	OTh	NCSG	VSG	NAP	
Unit	h	t NH3 / h	ratio	Pa	°C	mg N2O / Nm3	Nm3 / h	t HNO3	
Count	3,264	3,264	3,264	3,264	3,264	1,680	3,264		
Minimum		0.00	0.00	148.00	800	0.00	0		
Maximum		8.91	1.0	427,661.0	898	1,802.62	85,037		
Mean		7.61	0.11	369,363.2	884	701.59	74,778		
Standard deviation		2.138	0.09	89,050.72	24	506.5	19,326		
95% confidence level (1.96 * Std.dev.)		4.19	0.18	174,539.41	47	993	37,879		
Sum	3,264								86,488.25
Limits acc. to consistency check									
Lower limit									
Upper limit									

According to this Query 1, the NAP value of Project campaign 8 is 86,488.25 t of nitric acid

Query 2: Elimination of faulty data outside operational limits

In this query (Query 2), the operational limits of the plant are applied. Lines of data in which at least one value indicates that the plant is out of operation (trip values) are completely eliminated from further analysis. The design “trip” temperature, i.e. the temperature inside the ammonia oxidation reactor below which the plant shuts down automatically has been applied to exclude such lines of data. During the project, the “trip temperature” of 820°C will be applied as the exclusion criterion for determining those hours during which the plant was offline during a campaign.

N.DBMS Project Campaign Calculation Project: AEL No. 11, Johannesburg, South Africa Campaign: C 24 24.03.11 - 06.08.11									
Project campaign 8 Query 2: With operational limits 152									
Parameter	OH	AFR	AIFR	Oph	OTh	NCSG	VSG	NAP	
Unit	h	t NH3 / h	ratio	Pa	°C	mg N2O / Nm3	Nm3 / h	t HNO3	
Count	3,037	3,037	3,037	3,037	3,037	1,564	3,037		
Minimum		0.01	0.04	33,041.00	821	56.81	0		
Maximum		8.91	0.13	427,661.0	898	1,802.62	85,037		
Mean		8.16	0.10	391,584.4	890	747.82	79,682		
Standard deviation		0.705	0.004	28,515.703	9.0	492	6,432		
95% confidence level (1.96 * Std.dev.)		1.382	0.008	55,890.778	17.6	965	12,607		
Sum	3,037								86,488.25
Limits acc. to consistency check									
Lower limit					820				
Upper limit									

As a result of this query the number of operation hours OH of Project campaign 8 is 3,037 h.

Query 6: application of confidence interval to eliminate outliers

The 95% confidence interval for NCSG and VSG values is derived and the outliers excluded individually for VSG and NCSG. Hence, the remaining number of data sets may differ between NCSG and VSG.

N.DBMS Project Campaign Calculation Project: AEL No. 11, Johannesburg, South Africa Campaign: C 24 24.03.11 - 06.08.11									
Project campaign 8 Q6: Q2 + confidence levels 156 160 152									
Parameter	OH	AFR	AIFR	Oph	OTh	NCSG	VSG	NAP	
Unit	h	t NH3 / h	ratio	Pa	°C	mg N2O / Nm3	Nm3 / h	t HNO3	
Count						1,543	2,953		
Minimum		0.007	0.04	33,041.00	821	56.81	67,365		
Maximum		8.91	0.13	427,661.0	898	1,709.64	85,037		
Mean		8.16	0.10	391,584.4	890	734.30	80,653		
Standard deviation		0.705	0.004	28,515.703	9.0	482	2,117		
95% confidence level (1.96 * Std.dev.)		1.382	0.008	55,890.778	17.6	944	4,149		
Sum	3,037								86,488.25
Limits acc. to consistency check									
Lower limit					820	0.00	67,075		
Upper limit						1,712.40	92,288		
Correction factors resulting from QAL2						0.9900	0.9600		
= VSG * NCSG * Oh * 10 ⁻⁹							t N2O	170.94	
= PE / NAP * 10 ⁻³							kg N2O / t HNO3	1.976	

As a result of this query the mean NCSG value for Project campaign 8 is 734.30 mg N2O / Nm3

As a result of this query the mean VSG value for Project campaign 8 is 80,653 Nm3 / h

As a result of this query the result for EFn for Project campaign 8 is 1.976 kg N2O / t HNO3

Relevant Project Emissions (PE_n) and respective Project Emission Factors (EF_n)

The resulting project emissions (PE_n) and project emission factor (EF_n) for the project campaigns covered by this monitoring report are:

Campaign	PE	EF_n
8 ^h project campaign	170.94 tN ₂ O	1.976 kgN ₂ O/tHNO ₃

Project Campaign Length

If the length of each individual project campaign CL_n is longer than or equal to the average historic campaign length CL_{normal} or to the baseline campaign length whichever is shorter, then all N₂O values measured during the baseline campaign can be used for the calculation of EF (subject to the elimination of data from the operational limits analysis, see above under recalculation of Baseline Emission factor).

Since for the project campaign 8 (PC8) CL_n < CL_{BL}, EF_{BL} is recalculated by eliminating those N₂O values that were obtained during the production of tonnes of nitric acid beyond the CL_{BL} (i.e. the last tonnes produced) from the calculation of EF_{BL}. See section : *New calculation of Baseline emissions factor due to CL_n < CL_{BL}* above.

E.3. Leakage calculation

>>

No leakage occurs under this project type.

E.4. Emission reductions calculation / table

>>

Emission reductions

A *moving average emissions factor* must be calculated at the end of a campaign n as follows:

$$EF_{ma,n} = (EF_1 + EF_2 + \dots + EF_n) / n$$

This process is repeated for each campaign such that a moving average, EF_{ma,n}, is established over time, becoming more representative and precise with each additional campaign.

To calculate the total emission reductions achieved in a campaign according to the formula below, the higher of the two values EF_{ma,n} and EF_n shall be applied as the emission factor relevant for the particular campaign to be used to calculate emissions reduction s (EF_p). Thus:

If EF_{ma,n} > EF_n then EF_p = EF_{ma,n}

If EF_{ma,n} < EF_n then EF_p = EF_n

In addition a campaign-specific *minimum emissions factor* (EF_{min}) shall be used to cap any potential long-term trend towards decreasing N₂O emissions that may result from a potential built up of platinum deposits. After the first ten campaigns of the crediting period of the project, the lowest EF_n observed during those campaigns will be adopted as a minimum emission factor (EF_{min}). If any of the later project campaigns results in a EF_n that is lower than EF_{min}, the calculation of the emission reductions for that particular campaign shall use EF_{min} and not EF_n. As this project campaign of this current monitoring period is only the 8th project campaign consideration of EF_{min} is not yet of relevance.

The emission reductions for the project activity during this monitoring period are determined by deducting the campaign-specific emission factor from the baseline emission factor and multiplying the result by the production output of 100% concentrated nitric acid over the campaign period and the GWP of N₂O according to:

$$ER = (EF_{BL} - EF_p) * NAP * GWP_{N_2O} * 10^{-3} \text{ (tCO}_2\text{e)}$$

Where:

Variable	Definition
-----------------	-------------------

ER	Emission reductions of the project for the specific campaign (tCO ₂ e)
NAP	Nitric acid production for the project campaign (tHNO ₃). The maximum value of NAP shall not exceed the design capacity.
EF _{BL}	Baseline emissions factor (kgN ₂ O/tHNO ₃)
EF _p	Emissions factor used to calculate the emissions from this particular campaign (i.e. the higher of EF _{ma,n} and EF _n) (kgN ₂ O/tHNO ₃)
GWP _{N₂O}	Global Warming Potential of N ₂ O (310 tCO ₂ e/tN ₂ O)

The resulting emission reductions (ER) for the project campaign covered by this monitoring report and all relevant monitoring results are summarized in the table below:

		Project campaign 8 (PC8): 24/03/2011 - 06/08/2011
NCSG _{BL}	mg/Nm ³	1,598.97
QAL2 NCSG		1.104
VSG _{BL}	Nm ³ /h	72,468
QAL2 VSG		1.010
OH _{BL}	h	4,950
NAP _{BL}	t HNO ₃	134,700
BE	t N ₂ O	639.561
UNC		3.99
EF_{BL}	kg N₂O/t HNO₃	4.559
NCSG _n	mg/Nm ³	734.30
QAL2 NCSG		0.99
VSG _n	Nm ³ /h	80,653
QAL2 VSG		0.960
OH _n	h	3,037
NAP _n	t HNO ₃	86,488
PE _n	t N ₂ O	170.94
EF _n	kg N ₂ O/t HNO ₃	1.976
EF _{ma,n}	kg N ₂ O/t HNO ₃	0.985
EF _{min}	kg N ₂ O/t HNO ₃	n/a
EF_p	kg N₂O/t HNO₃	1.976
GWP	tCO ₂ e/tN ₂ O	310.00
ER	tCO₂e	69,230
Total ER for the monitoring period		69,230

Comparison of design capacity and actually achieved production during this monitoring period

The design capacity of the plant is 775 metric tonnes per day, operating 365 days per year. This equals a total production of 123,225 tonnes for a period of 159 days. Therefore the factual production of 86,448 tonnes during this monitoring period is below the design capacity of the plant.

E.5. Comparison of actual emission reductions with estimates in the CDM-PDD

>>

This section shall include a comparison of actual values of the emission reductions achieved during the monitoring period with the estimations in the registered CDM-PDD.

Item	Values applied in ex-ante calculation of the registered CDM-PDD	Actual values reached during the monitoring period
Emission reductions (tCO ₂ e)	115,639	69,230

E.6. Remarks on difference from estimated value in the PDD

>>

The estimated annual emission reductions as of the registered PDD are 265,460 tCO₂e. The total monitoring period covers 159 days and the respective estimated emission reductions for the monitoring period are 115,639 tCO₂e. The actual emission reductions of 69,230 tCO₂e achieved during this monitoring period are below the estimated result. The reason for this is based on higher baseline emissions due to a damage of the primary gauze. Due to a high demand of nitric acid and due to the delivery time for a replacement gauze it was not possible to start a new campaign with a fresh gauze earlier. The nitric acid production of 86,488 tonnes of HNO₃ was considerably below the estimated amount of 102,848 tonnes of HNO₃ as estimated for the same period in the PDD. Secondly the exclusion of NCSG results for the period 18/04/2011 – 23/06/2011 due to a leakage in the sampling system results in a considerably higher project emission factor for this campaign.

- - - - -

History of the document

Version	Date	Nature of revision
01	EB 54, Annex 34 28 May 2010	Initial adoption.
Decision Class: Regulatory Document Type: Guideline, Form Business Function: Issuance		